3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Alahalli Kodagikere Regd. No. 150 of Kolar Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The tenderer must quote specific rates for all items both in words and in figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for restoring Alahalli Kodagikere Register No. 150 of Kolar Taluk.

No.	Items of work.	Per	Quantity.
	Bund.		
1	Earthwork including watering and tamping with lead and lift complete.	C'yd.	3,800
2	Turfing	S.yd.	3,828
3	Resetting old stone with new jelly	Cyd.	760
4	New stone work	"	1,470
5	Fixing new grade stones as per details	No.	10
6	Fixing old grade stones dor	"	22
7	Fixing old Index stones do	"	22
8	Fixing new Index stones do	"	10
9	Removing and refixing old register No. stone	"	1
10	Fixing new gauge stone as per details	"	1
11	Fixing new B. M. stones	"	2
12	Cutting grips to old bund	Grade	30
	Total bund ...		
	Sluice No. 1.		
	Patch repairs found necessary during execution and providing plug and rod with locking arrangement.	Lump	sum
	Sluice No. 2.		
	Cutting open bund, examining and repairing sluice and providing plug and rod with locking arrangement.	Lump	sum
	Total Sluices No. 1 and 2 ...		
	Waste Weir.		
1	Earthwork	Cydr	132
2	Concrete in surki mortar	Cft.	657
3	Burnt brick in surki mortar	"	1,070
4	Surki mortar plastering	Sqr.	12·92
5	Burnt stone slabs 6" thick	S.ft.,	757
6	New stone work	C.yds.	252
7	Providing jaggle joints	No.	23
8	Draft and approach clearing	Lump	sum
	Total waste weir ...		